MYSORE CITY IMPROVEMENT TRUST BOARD.

Dated 24th June 1904.

Notice is hereby given that sealed tenders will be received at the office of the Chairman of the Board of Trustees for the Mysore City Improvements, up to the 15th July 1904, for the—(1) Construction of drains and works pertaining to them. An approximate estimate of quantities is given in the accompanying statement. These quantities referred to therein are not guaranteed. The work should be completed by the end of 30th June 1905.

2. The plans, detailed estimate, and conditions may be seen at the office of the Chairman of the Board of Trustees for the Mysore City Improvement, between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Chairman's office. The tenders should be accompanied by a statement in the form appended, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "(1) Tender for the drainage of new Doddaholagere to the south of Veerannah Weavers' lines," Mysore City, in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Trustees for the Improvements of the Mysore City, who do not bind themselves to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Chairman's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Statement showing the quantity of drainage works to be done in new Doddaholagere, south of Veerannah Weavers' lines:—

No.	Items of work.	Per.	Approximate quantity.
1.	Earthwork, excavation, soft soil for constructing drain of semi-peg-top section, etc.	C. yds.	2,315
2.	Do hard soil do do ...	„	905
3.	Do rocky soil do do ...	„	127
4.	Machine ground surki mortar concrete for constructing drain of semi-peg-top section.	C. ft.	48,690
5.	Do plastering rendering with cement smooth for drains.	Sqr.	570·94
6.	Burnt stone slabs 3″ to 4½″ thick dressed at joints for covering drains at the crossing of road junction.	S. ft.	8,575
7.	Laying of stoneware glazed pipe 6″ diameter including fitting and carting (when pipes are supplied).	R. ft.	1,170
8.	Machine ground surki mortar concrete for filling foundations of silt trap, manholes, latrines and etc.	C. ft.	3,814
9.	Do chunam mortar concrete for filling foundations of latrines.	„	644
10.	Burnt brick in machine ground surki mortar for constructing silt traps, manholes, etc.	„	4,359
11.	Do do chunam mortar for constructing latrines.	„	2,896
12.	Machine ground surki mortar plastering for manholes and latrines.	Sqr.	65·12
13.	Plastering with cement for flushing tanks	„	8·60
14.	Coping with burnt brick in machine ground chunam mortar and plastering.	R. ft.	294
15.	Do stone slabs 3″ thick dressed at joints, set in mortar.	S. ft.	160
16.	Burnt stone slabs 6″ thick dressed at joints for covering drains ...	„	85
17.	Teakwood doors (3′ × 6′) including frame to the washing platform at latrines.	Each.	4

Machinery for grinding mortar will be made available, the tenderer bearing the charges for the preparation of the mortar.

Dated 24th June 1904.

Notice is hereby given that sealed tenders will be received at the office of the Chairman of the Board of Trustees for the Mysore City Improvements, up to the 15th July 1904, for the—

(1) For cutting, forming and gravelling roads. An approximate estimate of quantities is given in the accompanying statement. These quantities referred to therein are not guaranteed. The work should be completed by the end of 30th June 1905.

2. The plans, detailed estimate, and conditions may be seen at the office of the Chairman of the Board of Trustees for the Mysore City Improvement between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Chairman's office. The tenders should be accompanied by a statement in the form appended, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "(2) Tender for cutting, forming and gravelling roads of New Doddaholageri to the south of Veerannah Weavers' lines" Mysore City, in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Trustees for the Improvements of the Mysore City, who do not bind themselves to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Chairman's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Statement showing the quantity of cutting, forming and gravelling roads in New Doddaholageri south of Veerannaha's Weavers' lines:—

No.	*Items of work.*	*Per.*	*Approximate quantity.*
1.	Earthwork cutting for opening roads	C. yds.	8,000
2.	Forming and gravelling roads 6" thick, including carting and consolidating.	S. yds.	132,366
3.	Planting avenue trees and maintaining them one season ...	Each.	...

D. SITARAM RAO, *Chairman.*

MORTUARY REGISTER.

FOR THE WEEK ENDING 10TH JUNE 1904.

Bangalore City.			*Mysore City.*		
Estimated population according to the Census of 1901.	Males	35,964	Estimated population according to the Census of 1901.	Males	34,328
	Females	33,483		Females	33,783
	Total	69,447		Total	68,111

Diseases.	M.	F.	Total.	Diseases.	M.	F.	Total.
Plague	...	...	...	Plague	...	...	...
Cholera	...	...	...	Cholera ...	...	...	...
Small-pox	...	...	...	Small-pox ...	...	...	...
Fevers	5	6	11	Fevers	2	1	3
Bowel-complaints ..	...	2	2	Bowel-complaints ...	3	2	5
Suicide	...	...	...	Suicide	...	1	1
Wounding	...	...	...	Wounding	...	....	...
Accident	...	...	...	Accident	...	1	1
Snake-bite or killed by wild beasts.	...	...	...	Snake-bite or killed by wild beasts.	...	...	...
All other causes ..	22	14	36	All other causes ..	12	11	23
Total ..	27	22	49	Total ...	17	16	33
Births during the week ...	14	12	26	Births during the week ..	12	8	20

T. S. NANJAPPA,
for *Offg. Senior Surgeon & Sany. Comr. with the Govt. of Mysore.*